



Consumer Response Group

6500 W. Cortland Street * Chicago, IL 60707 * Phone: 773-889-8870 * FAX: 773-622-2269

July 18, 2007

Page 1 of 1

TECHNICAL SERVICE BULLETIN

10053

MODEL(S): 150 GTL DX

DESCRIPTION: When transmitting, there is sometimes a "pop" in the modulation.

ACTION: Change C114 to a 47 μ F capacitor. If C114 is missing, then install a 47 μ F capacitor into position.

ADJUSTMENTS: None.

NOTES: None.